



Hames Music

370 Peachoid Rd
Gaffney, SC 29341

First United Methodist Church
Mr. Erwin Hittel, Trustee
325 N. Broad Street
Brevard, NC 28712

C06029 828-883-9025 Fax: 828-885-2347

Project Number 1743

12/21/2007 Page: 1 **Confidential Proposal**
864-487-7766 864-489-1135 fax

First United Methodist Church
Mr. Erwin Hittel, Trustee

325 N. Broad Street
Brevard, NC 28712

Project Title: Improvements to Sound & Acoustics

Sound System: Digitally Steerable Line Arrays

(Scope of Work: Remove existing (2) main speakers from above pulpit & lectern and provide to owner for storage and possible re-use in fellowship hall. Install new EAW DSA line arrays in spaces between square fluted columns by pulpit & lectern; install signal and control wiring. Program speakers to optimize coverage for main floor seating. Test and calibrate complete system for optimum performance. Demonstrate system and provide operator training. Deliver project binder with documentation and system configuration software.

Eastern-0005480-00	2 EAW DSA250 White 115 V; Digitally Steerable Line Array Speaker	4,777.50	9,555.00
Eastern-0005483-00	2 DSA230 White Low Frequency Speaker* (*-Recommended Option for Best Performance)	3,477.50	6,955.00
	250 Installation CAT5 Cable	0.27	67.50
Shure-WCE6IT	1 Tan, Countryman E6-I series Omnidirectional Mic for 2nd Wireless		367.88
HORIM-LO-Z2 (BLACK)	250 2-Conductor CL Rated Installation Audio Cable	0.18	45.00
HAMEM-MISC100	1 Miscellaneous Installation Hardware & Connectors		135.00
	20 Installation	50.00	1,000.00
	12 Design, Programming, Testing, & Calibration	50.00	600.00
			=====
	Subtotal Sound System Project:		18,725.38



Hames Music

370 Peachoid Rd
Gaffney, SC 29341

Project Number 1743

12/21/2007 Page: 2 **Confidential Proposal**
864-487-7766 864-489-1135 fax

Acoustic Wall Panels

Scope of Work: Install fabric covered acoustical wall panels adjacent to windows and in balcony areas for the purpose of controlling excessive reverberation.

	20 30"W X 8'H X 1" D Alphasorb Fabric Wrapped Wall Panel	233.89	4,677.80
	10 48" W X 48"H X 1"D Alphasorb Fabric Wrapped Wall Panel	149.85	1,498.50
	30 Beveled Edges, Per Panel	14.00	420.00
	30 Metal Z-Clip Fasteners, Per Panel	27.00	810.00
HAMEM-MISC100	1 Miscellaneous Installation Hardware		135.00
	45 Panel Installation	50.00	2,250.00

Subtotal Wall Panels: -----
9,791.30

Shipping & Handling: 986.67 986.67

NC7 Local Tax 1,726.67

This Confidential Proposal is Valid for 90 Days. =====
\$31,770.02

Jim Deal, Hames Pro Div. Director

Subject to Terms and Conditions of Hames Pro Installation Agreeeme
Payment Terms are Net Due 15 Days from Receipt of Invoice.